

# **BUILDINGENERGY BOSTON**

---

## **Working Smarter Not Harder: The Power of Teamwork in Multifamily PH Projects**

**Michelle Apigian, ICON Architecture**

**Moses Cordeiro, Dellbrook JKS**

**James Petersen, Peterson Engineering**

**Zoe Weinrobe, 2Life Communities**

**Ashley Wisse, New Ecology**

*Curated by Nick Pittman and Keihly Moore*

---

**Northeast Sustainable Energy Association (NESEA) | March 21, 2025**



NESEA Conference  
March 21, 2025

## Working Smarter Not Harder: The Power of Teamwork in Multifamily Passive House Projects





# Learning Objectives

1. Understand the diverse perspectives and priorities of various Passive House project team members.
2. Clearly identify the roles and responsibilities of each Passive House project team member.
3. Describe the complexities of collaborating effectively on multifamily Passive House projects.
4. Adapt the presented approach to address challenges on your projects and achieve Passive House certification.





NESEA Conference  
March 21, 2025


## Panelist Introductions





---



## Owner/Developer

Zoe Weinrobe  
Chief of Real Estate  
2Life Communities











---

Architect

Michelle Apigian  
Managing Principal  
ICON ARCHITECTURE  
CPHC





## DESIGN



- Orientation
- Surface to Volume
- Envelope
- Systems

## DOCUMENT

- Boundary
- Continuity
- Systems
- Details by trade

## BUILD

- Schedule + Sequence
- Mockups
- Testing
- Commissioning



## COMMUNICATION

---

MEP/FP

James Petersen  
Principal  
Petersen Engineering, Inc.  
P.E.



---

## MEP/FP

1

Verified air barrier => low infiltration in H/C load calc

2

Thermal barrier knowledge => higher R-values in H/C load calculations

3

Simple building forms => downsized and simplified HVAC

4

A good enclosure provides comfort => reduced burden on heating system to provide comfort

5

Open communications => a truly integrative design process

6

Integrated enclosures with HVAC => good outcomes in numerous ways





---

## General Contractor

Moses Cordeiro  
Senior Superintendent  
Dellbrook JKS



# General Contractor

## PASSIVE HOUSE GUIDE

### Division: 7 Thermal + Moisture

#### Weather Resistant Barrier



- Ensure no bubbling, fish mouths, and rips
- Clean and adhered tape
- Carefully sealed penetrations
- All panel gaps are greater than 1/8" with backer rod before tape
- Place thermal pads where required
- On the ZIP systems all nail heads must be sealed

## PASSIVE HOUSE GUIDE

### Division: 1 - General Requirements

#### Training and Mock-up



- Foundation WRB and insulation training – after relevant trades have been bought and the foreman of each relevant trade has been assigned.
- Mockup inspection is a critically important step; include in all estimates.
- Final product should be perfect to establish project's trades.

## PASSIVE HOUSE GUIDE

#### Testing and Closeout

- Confirm with the HVAC team that they are prepared to complete the attached example of ENERGY STAR MFNC HVAC Functional testing report
- Early on and throughout the project DBJKS will need to fill out the Building Efficiency Resources – Sampling Project Application for the PHIUS team.

DELLBROOK JK5					
Item	Unit	Quantity	Unit Price	Total Price	Notes
1.00	1.00	1.00	1.00	1.00	1.00
2.00	2.00	2.00	2.00	2.00	2.00
3.00	3.00	3.00	3.00	3.00	3.00
4.00	4.00	4.00	4.00	4.00	4.00
5.00	5.00	5.00	5.00	5.00	5.00
6.00	6.00	6.00	6.00	6.00	6.00
7.00	7.00	7.00	7.00	7.00	7.00
8.00	8.00	8.00	8.00	8.00	8.00
9.00	9.00	9.00	9.00	9.00	9.00
10.00	10.00	10.00	10.00	10.00	10.00
11.00	11.00	11.00	11.00	11.00	11.00
12.00	12.00	12.00	12.00	12.00	12.00
13.00	13.00	13.00	13.00	13.00	13.00
14.00	14.00	14.00	14.00	14.00	14.00
15.00	15.00	15.00	15.00	15.00	15.00
16.00	16.00	16.00	16.00	16.00	16.00
17.00	17.00	17.00	17.00	17.00	17.00
18.00	18.00	18.00	18.00	18.00	18.00
19.00	19.00	19.00	19.00	19.00	19.00
20.00	20.00	20.00	20.00	20.00	20.00
21.00	21.00	21.00	21.00	21.00	21.00
22.00	22.00	22.00	22.00	22.00	22.00
23.00	23.00	23.00	23.00	23.00	23.00
24.00	24.00	24.00	24.00	24.00	24.00
25.00	25.00	25.00	25.00	25.00	25.00
26.00	26.00	26.00	26.00	26.00	26.00
27.00	27.00	27.00	27.00	27.00	27.00
28.00	28.00	28.00	28.00	28.00	28.00
29.00	29.00	29.00	29.00	29.00	29.00
30.00	30.00	30.00	30.00	30.00	30.00
31.00	31.00	31.00	31.00	31.00	31.00
32.00	32.00	32.00	32.00	32.00	32.00
33.00	33.00	33.00	33.00	33.00	33.00
34.00	34.00	34.00	34.00	34.00	34.00
35.00	35.00	35.00	35.00	35.00	35.00
36.00	36.00	36.00	36.00	36.00	36.00
37.00	37.00	37.00	37.00	37.00	37.00
38.00	38.00	38.00	38.00	38.00	38.00
39.00	39.00	39.00	39.00	39.00	39.00
40.00	40.00	40.00	40.00	40.00	40.00
41.00	41.00	41.00	41.00	41.00	41.00
42.00	42.00	42.00	42.00	42.00	42.00
43.00	43.00	43.00	43.00	43.00	43.00
44.00	44.00	44.00	44.00	44.00	44.00
45.00	45.00	45.00	45.00	45.00	45.00
46.00	46.00	46.00	46.00	46.00	46.00
47.00	47.00	47.00	47.00	47.00	47.00
48.00	48.00	48.00	48.00	48.00	48.00
49.00	49.00	49.00	49.00	49.00	49.00
50.00	50.00	50.00	50.00	50.00	50.00
51.00	51.00	51.00	51.00	51.00	51.00
52.00	52.00	52.00	52.00	52.00	52.00
53.00	53.00	53.00	53.00	53.00	53.00
54.00	54.00	54.00	54.00	54.00	54.00
55.00	55.00	55.00	55.00	55.00	55.00
56.00	56.00	56.00	56.00	56.00	56.00
57.00	57.00	57.00	57.00	57.00	57.00
58.00	58.00	58.00	58.00	58.00	58.00
59.00	59.00	59.00	59.00	59.00	59.00
60.00	60.00	60.00	60.00	60.00	60.00
61.00	61.00	61.00	61.00	61.00	61.00
62.00	62.00	62.00	62.00	62.00	62.00
63.00	63.00	63.00	63.00	63.00	63.00
64.00	64.00	64.00	64.00	64.00	64.00
65.00	65.00	65.00	65.00	65.00	65.00
66.00	66.00	66.00	66.00	66.00	66.00
67.00	67.00	67.00	67.00	67.00	67.00
68.00	68.00	68.00	68.00	68.00	68.00
69.00	69.00	69.00	69.00	69.00	69.00
70.00	70.00	70.00	70.00	70.00	70.00
71.00	71.00	71.00	71.00	71.00	71.00
72.00	72.00	72.00	72.00	72.00	72.00
73.00	73.00	73.00	73.00	73.00	73.00
74.00	74.00	74.00	74.00	74.00	74.00
75.00	75.00	75.00	75.00	75.00	75.00
76.00	76.00	76.00	76.00	76.00	76.00
77.00	77.00	77.00	77.00	77.00	77.00
78.00	78.00	78.00	78.00	78.00	78.00
79.00	79.00	79.00	79.00	79.00	79.00
80.00	80.00	80.00	80.00	80.00	80.00
81.00	81.00	81.00	81.00	81.00	81.00
82.00	82.00	82.00	82.00	82.00	82.00
83.00	83.00	83.00	83.00	83.00	83.00
84.00	84.00	84.00	84.00	84.00	84.00
85.00	85.00	85.00	85.00	85.00	85.00
86.00	86.00	86.00	86.00	86.00	86.00
87.00	87.00	87.00	87.00	87.00	87.00
88.00	88.00	88.00	88.00	88.00	88.00
89.00	89.00	89.00	89.00	89.00	89.00
90.00	90.00	90.00	90.00	90.00	90.00
91.00	91.00	91.00	91.00	91.00	91.00
92.00	92.00	92.00	92.00	92.00	92.00
93.00	93.00	93.00	93.00	93.00	93.00
94.00	94.00	94.00	94.00	94.00	94.00
95.00	95.00	95.00	95.00	95.00	95.00
96.00	96.00	96.00	96.00	96.00	96.00
97.00	97.00	97.00	97.00	97.00	97.00
98.00	98.00	98.00	98.00	98.00	98.00
99.00	99.00	99.00	99.00	99.00	99.00
100.00	100.00	100.00	100.00	100.00	100.00

---

## Sustainability Consultant

Ashley Wisse  
Director of Green Building  
Services  
New Ecology, Inc.  
CPHC, CPHB





# Balancing Certifications & Requirements



Resiliency


Mass.gov

Executive Office of Housing and Livable Communities (EOHLC)



# Passive House Certification Process

---





NESEA Conference  
March 21, 2025

## Integrated Project Team: Tools & Coordination





# Phius Design Best Practices: WUFI Modeling Inputs and Uses

Geometry	
Interior Conditioned Floor Area (iCFA)	129,926
Net Volume	1,184,935
Envelope Area	126,551
Average Window-to-Wall Ratio	20%

Renewable Generation	Units	
Solar PV (capacity)	kW	0
Solar PV (annual generation)	kWh/yr	0
Solar PV (coincident generation)	kWh/yr	0

Exterior Envelope	Units	
Roof	R	50
Above Grade Exterior Wall	R (effective)	21
Slab	R	16
Below Grade Exterior Wall	R	11
Exterior Floor	R	30
Adiabatic Wall/Floor	R	1
Fixed Windows	U (Whole Window)	0.15
	SHGC (Center-of-Glass)	0.40
Operable Windows	U (Whole Window)	0.17
	SHGC (Center-of-Glass)	0.40
Storefront	U (Whole Window)	0.40
	SHGC (Center-of-Glass)	0.40
Glass Doors	U (Whole Window)	0.57
	SHGC (Center-of-Glass)	0.40
Opaque Door	R	2.4

Ventilation	Units	
Dryer Exhaust	cfm	220
ERV Ventilation	cfm	11,558
ERV Power	W/cfm	1.2
ERV Recovery Efficiency	%	80%



# Roles & Responsibilities

<b>Passive House Roles and Responsibilities Matrix</b>							
Project: <b>PROJECT NAME, CITY, STATE</b>							
Owner: <b>CLIENT</b>							
Phase	CLIENT Owner	ARCHITECT Architect	SUSTAINABILITY CONSULTANT CPHC, PHIUS+ Verifier, HERS Rater	MEP MEP Engineer	GC General Contractor	CxA Commissioning Agent	PHIUS
<b>Feasibility Study</b>							
Register project with utility rebate program, provide feasibility contract			X				
Create SD drawing set with geometry, baseline MEP assumptions		X		X			
Develop preliminary WUFI Passive energy model and report			X				
Feasibility review meeting	X	X	X	X			
<b>Project Set-up</b>							
Request PHIUS+ Certification Contract			X				
Review and sign PHIUS+ Certification Contract	X						
Payment sent by check or by PayPal link	X						
Register project into PHIUS project database, set up DropBox folders			X				
Complete Verifier Letter of Intent			X				
<b>Pre-Certification</b>							
Develop and manage WUFI Passive energy modeling, ongoing			X				
Complete HERS energy model to generate a preliminary HERS Index Score for ENERGY STAR MFNC, submit to HERS provider for verification and preliminary HERS Certificates			X				
ENERGY STAR MFNC Design Checklist			X				
ENERGY STAR MFNC HVAC Design Checklist				X			
Coordinate and integrate feedback from energy modeling into project drawings		X		X			
Perform review and feedback during design for PHIUS, ENERGY STAR, EPA Indoor airPLUS, and DOE ZEBU requirements			X				

# Roles & Responsibilities



## ENERGY STAR Multifamily New Construction National HVAC Functional Testing Checklist <sup>1</sup>, Version 1 / 1.1 / 1.2 (Rev.04)

<span style="display:inline-block; width:15px; height:10px; background-color:cyan; border:1px solid black;"></span> Not applicable to most projects	<span style="display:inline-block; width:15px; height:10px; background-color:orange; border:1px solid black;"></span> Manufacturer's Rep
<span style="display:inline-block; width:15px; height:10px; background-color:magenta; border:1px solid black;"></span> TAB Contractor	<span style="display:inline-block; width:15px; height:10px; background-color:lightgreen; border:1px solid black;"></span> New Ecology
<span style="display:inline-block; width:15px; height:10px; background-color:yellow; border:1px solid black;"></span> Commissioning Agent	<span style="display:inline-block; width:15px; height:10px; background-color:purple; border:1px solid black;"></span> HVAC Sub

Revised 02/15/2024

<b>5.1 Installation Checks</b>		
5.1.1 Zone thermostat (or remote zone temperature sensor) in dwelling units, within the zone being served.	<input type="checkbox"/>	<input type="checkbox"/>
<b>5.2 Functional Testing</b>		
5.2.1 Measured zone temperature is within 5°F of zone temperature displayed on thermostat or sensor.	<input type="checkbox"/>	<input type="checkbox"/>
5.2.2 System turns on when there is a call for heat and heating is provided. System turns off when the heating setpoint has been met. <sup>7</sup>	<input type="checkbox"/>	<input type="checkbox"/>
If N/A, select the reason: <input type="checkbox"/> due to high ambient temperature OR <input type="checkbox"/> equipment lock-out	-	-
5.2.3 System turns on when there is a call for cooling and cooling is provided. System turns off when the cooling setpoint has been met. <sup>7</sup>	<input type="checkbox"/>	<input type="checkbox"/>
If N/A, select the reason: <input type="checkbox"/> due to low ambient temperature OR <input type="checkbox"/> equipment lock-out	-	-
5.2.4 Where OA inlets are connected to the dwelling unit HVAC system, a motorized damper is installed that closes when there is no call for ventilation or when fan is off.	<input type="checkbox"/>	<input type="checkbox"/>
<b>6. Shared VRF Outdoor Units</b> - This section must be completed for commercial-grade VRF outdoor units serving multiple dwelling units or common spaces.	<b>FT Agent Verified <sup>1</sup></b>	<b>N/A</b>
<b>6.1 Installation Checks</b>		
6.1.1 Pressure testing on refrigerant piping has been completed for this system. (indicate exact test in / test out pressure (psig) / time (hours)): _____ / _____ / _____	-	<input type="checkbox"/>
6.1.2 Vacuum testing has been completed. (indicate exact test in / test out pressure (psig) / time (hours)): _____ / _____ / _____	-	<input type="checkbox"/>
6.1.3 Refrigerant line lengths and height differences have been recorded from as-built shop drawings or field measured, and documentation of the measurement is available, if requested.	<input type="checkbox"/>	<input type="checkbox"/>
6.1.4 Indicate required additional charge amount (lbs): _____	-	<input type="checkbox"/>





---

## Construction Phase: Submittal Review Coordination

- 1 Direct distribution from online platforms (Procore, Newforma, etc.)
- 2 Submittal Comments Protocol – timing, method of organization of comments, how to indicate high-priority items.
- 3 CPHC must review all submittals – information can be hidden!
- 4 Document, Document, Document!



# Construction Phase: Submittal Review Coordination

PRODUCT DATA SUBMITTAL - SUSTAINABLE ATTRIBUTES REPORTING FORM													
THIS FORM IS REQUIRED TO BE SUBMITTED <i>WITH Product Data Submittals</i>													
You must include backup documentation such as <i>SPECIFIC</i> Product Data Sheets, Cut Sheets, Product Specific Letter from Manufacturer, etc. <b>DO NOT INCLUDE GENERIC MARKETING MATERIAL</b>													
PROJECT NAME:													
SUBCONTRACTOR:													
Specification Section:		Submittal Number:											
Project Product Data				Materials and Resources Information									
REQUIRED for ALL Products in Specs CSI Divisions 3-10, 31 Foundations, 32 Paving, 32 Site Improvements, 32 Plantings & VOCs in 22, 23													
Product Name/Model	Manufacturer, City, State	Product Costs <sup>1</sup> (only exclude install labor) (\$)	Product Specific (PS) or Industry Wide (IW) Environmental Product Declaration (EPD) <sup>2</sup> ?	FSC Certified <sup>4</sup> Wood Products? (%)	Post-Consumer Recycled Content <sup>5</sup> (%)	Pre-Consumer Recycled Content <sup>6</sup> (%)	3rd-party verified Manufacturer Corporate Sustainability Report?	Declare Label with ingredient disclosure greater than 1000 ppm?	Fully Declared HPD to 1000 ppm Declaration <sup>3</sup> included?	C2C version (2.1.1 or 3.0) Level of Certification			
Ex. ABC Product	ABC, Inc.	\$ XX,XXX	PS / IW	%	%	%	Yes / No	Yes / No	Yes / No	Yes / No			



# Construction Phase: Submittal Review Coordination

Date Reviewed	Submittal Number	Submittal Title	Subrina Comments (LEED)	Spencer Comments (Phius)	Paul / Mark Comments
1/24/23	#1A_237200-3.0	BLDG 1A - Energy Recovery Ventilator (ERV-1, ERV-2, ERV-3, and ERV-4)	ventilation prereq flow rates (7.5 cfm / 100 square feet, ERV exhaust at ~9.5 cfm / 100 square feet)	equipment for ERV 4 (serving a garage I would assume), and CO2 detector in exhaust intake - LEED credit?	
				NA	
1/25/23	#1A_033000-5.1	BLDG 1B - Garage to 2nd Floor SOG & SOMD Shop Drawings	N/A	SL question: is there anything in the SOG submittals we would ever look for under PH, or is it something that has to be evaluated on site when looking at the vapor barrier?	I have taken a look at the SOG and SOMG shop drawings for 1B and I don't have any feedback to add. As we all learn, we may have additional items to note or offer feedback
1/25/23	#1A_033000-4.1	BLDG 1A - Ground & 2nd Floor SOMD Shop Drawings	N/A	NA	
1/25/23	#1A_033000-3.1	BLDG 1A - SOG Shop Drawings	N/A	NA	I am not able to see the actual submittal document on Procore on 1/25/2023
			I found separate submittals for SpecSeal LCI Sealant and Pensil 300 Sealant, and neither seem to meet CA Section 01350. They're both used for firestopping in floor assemblies. Does this mean we can't get the point for EQ Low-Emitting Products: Adhesives and Sealants?		
1/25/23	#1A_078410-1.1	BLDG 1A/1B - Plumbing Firestopping	<b>Frank to check; if it's rejected already, we can share our comments like: "when it comes back, we hope the CA Section 01350 will be met"</b>	Had to resubmit firestopping, wanted only one manufacturer, I don't see a new one	I think this submittal already had a comment on it from Kevin Collins.
1/25/23	#1A_237200-004.0	BLDG 1A - Energy Recovery Ventilator (ERV-5 and 6)	Originally had MERV 8 filters written for the OA side of the ERV, but there's an edited note identifying that they have to be MERV 13.	ECM and MERV 8/13 filters, ES compliant	If this submittal matches the design drawings, then I think we have no objection.
1/25/23	#1A_084410-1.0	BLDG 1A-1B Curtain Wall Pressure Plate System	N/A; fiberglass plate isn't recycled material so not eligible for MR Environmentally Preferable Products		FS Note - I would like to make sure that this item is for use in 1A only. I don't know who this will be used, and would like to confirm.
1/31/23	#1A_088000-2.0	BLDG 1A-1B Storefront Glass (Solarban 60) Product Data	Note: forwarded from Steve for us to review N/A	Winter U-0.24, Summer U-0.22, SHGC-0.39 Roughly matches storefront examples in WUFI model report, is there anything else that needs to be confirmed?	Phius Design Cert Feedback form shows U-glass of 0.29. This submittal shows U-value 0.24 and SHGC of 0.39. <b>New Ecology has no objections</b>
1/31/23	#1A_088000-1.0	BLDG 1A-1B Window Film Product Data	Note: forwarded from Steve for us to review N/A	SHGCs for film at .48, .46, and .44 depending on thickness, how does this influence window assemblies?	New Ecology would like to ask what this material is intended to do, and where it will be used on the project.
1/31/23	#1A_084110-1.0	BLDG 1A Exterior Storefront Shop Drawings	Tremco Spectrem 1&2 has Greenguard Gold certification which means it meets CA Section 01350.	sealants are only recommended for indoor airplus	
1/31/23	#1A_084110-2.0	BLDG 1B Exterior Storefront Shop Drawings	Tremco Spectrem 1&2 has Greenguard Gold certification which means it meets CA Section 01350.		Building 1B was Phius Design Certified with Kawneer 451UT and Kawneer Insulpour 50 materials. Please provide CRF rating and u-values for materials to be used on MH1B. I will need specific materials to be Phius certified.
1/31/23	#1A_081210-1.0	BLDG 1A-1B Interior Aluminum Frames Product Data	N/A		
1/31/23	#1A_081210-2.0	BLDG 1A Interior Aluminum Frame Shop Drawings	N/A		
1/31/23	#1A_081210-3.0	BLDG 1B Interior Aluminum Frame Shop Drawings	N/A		
1/31/23	#1A_084110-3.0	BLDG 1A-1B Exterior Aluminum Storefront and Entrances Product Data	N/A		Building 1B was Phius Design Certified with Kawneer 451UT and Kawneer Insulpour 50 materials. Please provide CRF rating and u-values for materials to be used on MH1B. Please show compliance with 084110-3 section J. 1B will need specific materials to be Phius certified.
1/31/23	#1A_323000-2.0	BLDG 1A/1B - Steel Bollards	N/A		
1/31/23	#1A_142100-5.0	BLDG 1A - Elevator 1 & 2 Revised Power Confirmation Letter (VE)	N/A		
1/31/23	#1A_142100-6.0	BLDG 1B - Elevator 1, 2 & 3 Revised Power Confirmation Letter (VE)	N/A		
1/31/23	#1A_085310-3.0	BLDG 1A/1B - Window Install Qualification	N/A		
1/31/23	#1A_085310-1.2	BLDG 1A - UPVC Windows	N/A		On page 1 of the Building 1A shop drawings there is a box checked that this is not a LEED project. We note for the record that Building 1A is a LEED project.
1/31/23	#1A_085310-2.1	BLDG 1B - UPVC Windows (Revised for Record)	N/A		

# Construction Site Coordination

321	MEP Coordination	363	Waterproofing, Backfill Foundation Walls	10 d	Thu 10/13/22	Wed 10/26/22	W
322	Passive Inspections Building E	364	Prep & Place Slab on Grade		Thu 11/17/22	Wed 11/23/22	T
323	ERV's / HVAC	365	Site Utilities		Wed 10/5/22	Fri 4/14/23	W
324	Zip Sheathing / Envelope	366	Install Site Utilities	30 d	Wed 10/5/22	Wed 11/16/22	W
325	Roof Membrane	367	Install Gas Meters	10 d	Mon 4/3/23	Fri 4/14/23	
326	Draft Seal / Firestopping	368	Structure	60 days	Wed 10/5/22	Thu 2/2/23	W
	Closed Cell Insulation	369	CMU Shaft	15 d	Wed 10/5/22	Wed 10/26/22	W
	Insulation	370	Install CMU Shaft	15 d	Wed 10/5/22	Wed 10/26/22	W
	Windows / Doors	371	Framing	45 d	Thu 12/1/22	Thu 2/2/23	
330	Blower Door Pre-Test	372	Frame - Level 1 Walls		Thu 12/1/22	Fri 12/9/22	
331	Blower Door	373	Frame - Level 2 Floors		Mon 12/12/22	Mon 12/19/22	M
332	Compartmentalization	374	Install Stairs	15 d	Mon 12/12/22	Fri 12/30/22	M
333	Passive Inspections Building D	375	Frame - Level 2 Walls	7 d	Tue 12/20/22	Wed 12/28/22	T
334	ERV's / HVAC	376	Frame - Level 3 Floors	6 d	Thu 12/29/22	Thu 1/5/23	T
335	Zip Sheathing / Envelope	377	Frame - Level 3 Walls	7 d	Fri 1/6/23	Tue 1/17/23	
336	Roof Membrane	378	Frame - Roof and Sheathing	12 d	Wed 1/18/23	Thu 2/2/23	V
337	Draft Seal / Firestopping	415	Rough in Electrical Boxes, Conduit	5 d	Mon 2/27/23	Fri 3/3/23	
338	Closed Cell Insulation	416	Level 3 Fit out	91 d	Mon 3/20/23	Thu 7/27/23	
339	Insulation	417	Electrical, Low Voltage and F.A. complete rough	10 d	Mon 3/20/23	Fri 3/31/23	
340	Windows / Doors		Remaining HVAC Rough, insulation	10 d	Mon 3/20/23	Fri 3/31/23	
341	Blower Door Pre-Test		Remaining Plumbing Rough	10 d	Mon 3/20/23	Fri 3/31/23	
342	Blower Door	420	Install Sprinklers	10 d	Mon 3/20/23	Fri 3/31/23	
343	Compartmentalization	421	MEP Inspections	2 d	Mon 4/3/23	Tue 4/4/23	
		422	Remaining Pre-rock and Fire stopping	Wed 4/5/23	Fri 4/7/23		
		423	Building Department inspection	1 d	Mon 4/10/23	Mon 4/10/23	
		424	Insulation and Vapor Barrier	NEI inspection of first available section of insulation, prior to closure	4/11/23	Wed 4/12/23	
		425	Insulation Inspection		4/13/23	Thu 4/13/23	
		426	Hang GWB	NEI Midpoint	Fri 4/14/23	Wed 4/26/23	
		427	Finish Tape, Sand and ready	Compartmentalization Testing of First Available Unit(s)	Thu 4/20/23	Mon 5/1/23	
		428	Install Tile in Bathrooms		Fri 4/21/23	Tue 5/2/23	
		429	Prime Ceilings and Walls	5 d	Tue 5/2/23	Mon 5/8/23	

Mock-Ups?  
NEI would like to observe mock-up installations and testing, if available

5-7 days per building

Glen Brook Way (Phase 2) Buildings D and E  
Project # 22-0007

---

## Soft Cost Reduction and Team Efficiencies

- 1 Teamwork is the key to removing built-in overages and increased scope fees for duplicative work, repetitive discussions, etc.
- 2 Simplicity in Design is the heart of efficiency
- 3 ...to be continued in the next Panel Discussion.







NESEA Conference  
March 21, 2025

# Panel Discussion



---

## Panel Discussion

1

What are some outcomes of poor communication that you have experienced on a Phius project?

2

What is your preferred form of communication on a Phius project?

3

How can future project team members better support your role in a Phius project?

4

What is the biggest lesson that you and your team learned from a recent Phius Project?

5

What are some (1-2) visible improvements in teamwork and related outcomes since your first Phius project?





NESEA Conference  
March 21, 2025

## Questions from the Audience



  
**Zoe Weinrobe**

Chief of Real Estate  
2Life Communities

[zweinrobe@2lifecommunities.org](mailto:zweinrobe@2lifecommunities.org)

**Michelle Apigian**

Managing Principal  
ICON ARCHITECTURE

[mapigian@iconarch.com](mailto:mapigian@iconarch.com)

**James Petersen**

Principal  
Petersen Engineering, Inc.

[james@petersenengineering.com](mailto:james@petersenengineering.com)

**Moses Cordeiro**

Senior Superintendent  
Dellbrook JKS

[Mcordeiro@dellbrookjks.com](mailto:Mcordeiro@dellbrookjks.com)

**Ashley Wisse**

Director of Green Building Services  
New Ecology, Inc.

[wisse@newecology.org](mailto:wisse@newecology.org)

